



OFFICE OF
THE CITY ENGINEER
PHONE (650) 829-6652
FAX (650) 829-6689

City of South San Francisco

CITY COUNCIL 2018

LIZA NORMANDY, MAYOR
KARYL MATSUMOTO, MAYOR PRO TEMPORE
MARK ADDIEGO, COUNCILMEMBER
RICHARD A. GARBARINO, COUNCILMEMBER
PRADEEP C. GUPTA, PH.D. COUNCILMEMBER

MIKE FUTRELL, CITY MANAGER

NOTICE OF CONSTRUCTION – San Bruno Canal Bridge Closure

June 3, 2018

South Airport Blvd & North Access Rd San Bruno Canal Bridge Replacement Project

(City Project No. ST1301)
04-SM-0-SSF / BRLS-5177(030) / 0413000001L-N
DIR #226511

Dear Property Owner / Proprietor / Tenant / Resident:

As you know, the San Bruno Canal Bridge at Airport Boulevard bridge was closed on May 21, 2018, and traffic has been detoured since Monday, May 21, 2018. In order to relieve congestion, a temporary relief road connecting Beacon Street and North Access Road was implemented on Thursday, May 24, 2018. The relief roadway was aligned through the construction zone to facilitate the quick implementation.

Please be advised that **this temporary relief road will be closed indefinitely on Wednesday, June 6, 2018 after the rush hour** to facilitate the replacement construction of the bridge. Please log into City web-site at www.ssf.net for updates.

Sincerely,

A handwritten signature in blue ink that reads "Robert Hahn".

Robert Hahn, PE
Project Manager
City of South San Francisco
Department of Public Works



OFFICE OF
THE CITY ENGINEER
PHONE (650) 829-6652
FAX (650) 829-6689

CITY COUNCIL 2018

LIZA NORMANDY, MAYOR
KARYL MATSUMOTO, MAYOR PRO TEMPORE
MARK ADDIEGO, COUNCILMEMBER
RICHARD A. GARBARINO, COUNCILMEMBER
PRADEEP C. GUPTA, PH.D. COUNCILMEMBER

MIKE FUTRELL, CITY MANAGER

City of South San Francisco

PROJECT DESCRIPTION & LOCATION MAP:

The South Airport Boulevard Bridge over the San Bruno Canal at North Access Road and the 380 Freeway on ramp needs to be replaced due to its deteriorated condition. The initial bridge was built in 1949 on wooden piles. In 1975, the bridge was widened, and the new sections were supported on concrete piles. The City with the assistance of Caltrans has been successful in obtaining funding from the Federal Highway Administration (FHWA) for the design and construction.

CLOSURES & DETOURS:

The City conducted an inspection recently and determined that the pile column foundation (both wooden and concrete) exhibits advanced excessive deterioration. An ensuing bridge structural assessment concluded that the bridge is susceptible to failure under currently permitted vehicular loading. To protect the travelling public and construction workers who would be performing work beneath the bridge, the City will be closing the bridge immediately effective May 21, 2018, prior to performing the bridge replacement project instead of maintaining traffic over the bridge during construction.

The **bridge** was **closed effective May 21, 2018** and remain closed until the bridge replacement construction is completed at the end of 2018. The public is requested to **follow the detour signs** to navigate through alternative routes once the bridge is closed.

CONSTRUCTION SCHEDULE:

Construction Start: May 2018
Anticipated Completion: December 2018

PROJECT CONTACT INFORMATION:

Public Information Contact
Phone: (800) 462 9550
Email: info@vsceinc.com

CONTRACTOR INFORMATION

ProVen Management, Inc.
Andres Martin (GC Project Manager)
225 3rd St. Oakland, CA 94607
Phone: (510) 913-4564
Email: AMartin@ProVenManagement.com



CITY OF SOUTH SAN FRANCISCO CONTACT:

Robert Hahn (City Project Manager)
Phone: (650) 829-6660
Email: Robert.Hahn@SSF.net

Ron Oen, P.E. (Construction Manager / Resident Engineer)
Phone: (408) 296-5515
Email: ROen@BiggsCardosa.com